




UNDIVIDED MULTI-LANE ROADWAY




UNDIVIDED MULTI-LANE ROADWAY
WITH TWO-WAY LEFT TURN LANE








DIVIDED FOUR LANE ROADWAY



DIVIDED SIX LANE ROADWAY



<div>STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.</div>		<div>ENGLISH STANDARD DRAWING FOR PAVEMENT MARKINGS NON-SIGNALIZED INTERSECTIONS</div>		<div>ENGLISH STANDARD DRAWING FOR PAVEMENT MARKINGS NON-SIGNALIZED INTERSECTIONS</div>		<div>SHEET 1 OF 2 1205.04</div>
<div>DETAIL 1</div> 		<div>DETAIL 3</div>  <p>*2' WHITE MINI-SKIPS WHERE LANES ARE OFFSET, OR AT LARGE INTERSECTIONS</p>		<div>DETAIL 5</div>  <p>NOTE: DOUBLE YELLOW CENTER LINE, AND ARROW SYMBOLS IN MEDIAN CROSSOVER SHOULD BE USED WHEN WIDTH OF MEDIAN EXCEEDS 30 FT. OTHERWISE THEY ARE NOT REQUIRED.</p>		<div>LEGEND</div> <div><div>○ STOP SIGN</div><div>→ PAVEMENT MARKING SYMBOLS</div><div>● DIRECTION OF TRAFFIC FLOW</div><div>* OPTIONAL</div></div>
<div>DETAIL 2</div> 		<div>DETAIL 4</div>  <p>*2' WHITE MINI-SKIPS</p>		<div>GENERAL NOTES</div> <ul style="list-style-type: none">- PLACEMENT OF STOP BARS AT NON-SIGNALIZED INTERSECTIONS IS OPTIONAL, AT SIGNALIZED INTERSECTIONS STOP BARS SHALL BE USED.- STOP BARS SHOULD BE USED WHERE IT IS IMPORTANT TO INDICATE THE POINT BEHIND WHICH VEHICLES ARE REQUIRED TO STOP, IN COMPLIANCE WITH A STOP SIGN OR TRAFFIC SIGNAL.- STOP BARS, WHEN USED, SHOULD BE PLACED AT THE DESIRED STOPPING POINT, NO LESS THAN 4 FEET, OR MORE THAN 30 FEET FROM THE NEAREST EDGE OF THE INTERSECTING ROADWAY. TEN FEET IS AN OFTEN USED SETBACK DISTANCE.- STOP BARS SHOULD BE PLACED IN LINE WITH STOP SIGNS, HOWEVER, WHEN STOP SIGNS CANNOT BE LOCATED EXACTLY WHERE VEHICLES ARE EXPECTED TO STOP, THE STOP BARS SHOULD BE PLACED AT THE DESIRED STOPPING POINT.- YELLOW EDGE LINES SHOULD BE CONTINUED AROUND MEDIAN CROSSOVER RADI.		

d:\d1q\12050401.dgn May. 25, 1999 11:21:51

DETAIL 6

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
SIGNALIZED INTERSECTIONS


SHEET 2 OF 2
1205.04

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
SIGNALIZED INTERSECTIONS


SHEET 2 OF 2
1205.04

** SET BACK DISTANCES TO STOPBARS VARY
DEPENDING ON THE LOCATION OF SIGNAL
HEAD. 10 FEET IS GENERALLY USED AS
A MINIMUM SETBACK DISTANCE.



d:\idq\12050402.dgn May. 25, 1999 11:25:12






NOTE: TWO-LANE FHWV SCHOOL SYMBOL MAY ALSO BE USED AS SHOWN IN PART 7C-6 OF THE MUTCD


TWO-LANE WIDTH "SCHOOL"

REFER TO STD. 1205.10




LETTER HEIGHT = 10'-5"
LETTER WIDTH = 20"
SPACING = 10" MIN./30" MAX.
(USE EQUAL SPACING BETWEEN LETTERS AND CENTER ENTIRE SYMBOL IN LANES)

"ONLY"



SINGLE LANE "SCHOOL"


REFER TO STD. 1205.10










LETTER HEIGHT = 8'-4"
LETTER WIDTH = 16"
SPACING = 4" MIN./8" MAX.
(USE EQUAL SPACING BETWEEN LETTERS AND CENTER ENTIRE SYMBOL IN LANE)

RAILROAD RXR SYMBOL

REFER TO STD. 1205.11




LANE WIDTH (FEET)	WIDTH OF "X" (FEET)
8' ≤ W ≤ 9'	7'
9' < W ≤ 12'	8'
W > 12'	10'



DIRECTION OF TRAVEL
WORDS ARE CENTERED IN TRAVEL LANE

SPEED LIMIT (MPH)	DI STANCE "D" BETWEEN WORD SYMBOLS
35 OR LESS	40'
40 - 50	60'
55 OR GREATER	80'

DISTANCE "D" MAY BE ADJUSTED AS
NECESSARY FOR OPTICAL SPACING




- STANDARD CHARACTERS ARE 25 GRID UNITS HIGH AND 4 UNITS WIDE (EXCEPT LETTER "I" AND THE NUMBER "1" WHICH ARE 1 UNIT WIDE).
- VERTICAL STROKES ARE 1 UNIT WIDE, HORIZONTAL STROKES ARE 4 UNITS HIGH.
- THE SPACE BETWEEN CHARACTERS SHOULD BE 1 UNIT (MIN.) OR AS OTHERWISE SHOWN (OPTICAL SPACING MAY BE USED).
- STANDARD CHARACTER HEIGHTS ARE 8'-4" EXCEPT FOR THE 6' RAILROAD 'R' SYMBOL AND THE TWO-LANE 10'-5" SCHOOL SYMBOL.
- FOR 8'-4" HIGH CHARACTERS THE WIDTH IS 16" (USE 4" FOR EACH GRID SQUARE).
- FOR 10'-5" HIGH CHARACTERS THE WIDTH IS 20" (USE 5" FOR EACH GRID SQUARE).
- FOR 6' HIGH CHARACTERS THE WIDTH IS 11 1/2" (USE 2 7/8" FOR EACH GRID SQUARE).

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
STANDARD ALPHABET AND SYMBOLS FOR
HIGHWAY PAVEMENT MARKING (USDOT-FHWA)

SHEET 5 OF 7
1205.08



STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
STANDARD ALPHABET AND SYMBOLS FOR
HIGHWAY PAVEMENT MARKING (USDOT-FHWA)


SHEET 5 OF 7
1205.08

d:\idq\12050805.dgn May. 25, 1999 13:18:04

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
STANDARD ALPHABET AND SYMBOLS FOR
HIGHWAY PAVEMENT MARKING (USDOT-FHWA)

SHEET 6 OF 7
1205.08




STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ENGLISH STANDARD DRAWING FOR
PAVEMENT MARKINGS
STANDARD ALPHABET AND SYMBOLS FOR
HIGHWAY PAVEMENT MARKING (USDOT-FHWA)

SHEET 6 OF 7
1205.08


d:\idq\12050806.dgn May. 25, 1999 13:20:07




CHANNELIZING ISLAND SEPARATING TRAFFIC IN SAME DIRECTION
(CHEVRON)



MEDIAN ISLAND SEPARATING TRAFFIC IN OPPOSING DIRECTIONS




EDGE OF PAVEMENT OR SHOULDER ISLAND




- D-SPACING OF DIAGONAL LINES (SHOULD TYPICALLY BE EQUAL IN FEET TO THE POSTED SPEED LIMIT).
- ON INTERSTATE ROADWAYS SPACING OF DIAGONALS SHOULD BE INCREASED TO 200' OR MORE.
- SPACING OF DIAGONALS MAY BE ADJUSTED DEPENDING ON THE LENGTH OF THE ISLAND (OPTICAL SPACING MAY BE USED).

LOCATION OF "SCHOOL" MARKINGS




TWO-LANE, TWO-WAY ROADWAYS




FOUR LANE ROADWAYS
(DI V I D E D AND U N D I V I D E D)



SIX LANE ROADWAYS
(DI V I D E D AND U N D I V I D E D)



WHERE PEDESTRIAN CROSSWALKS ARE
REQUIRED IN SCHOOL AREAS HIGH VISIBILITY
CROSSWALKS SHALL BE USED.




GENERAL NOTES

- SINGLE LANE "SCHOOL" WORD MESSAGES MAY BE USED IN EACH APPROACH LANE.
- 24" WHITE TRANSVERSE LINES SHALL EXTEND ACROSS ALL LANES APPROACHING THE SCHOOL AREA, EXCEPT FOR TWO-LANE, TWO-WAY ROADWAYS WHERE THEY SHALL EXTEND ACROSS THE ENTIRE ROADWAY WHEN TWO-LANE MESSAGES ARE USED.
- THE 24" TRANSVERSE BANDS ARE NOT CONSIDERED PART OF THE SCHOOL MESSAGES PAY ITEM, AND WILL BE PAID FOR SEPARATELY.

STOP BAR LOCATION

15 FEET IN ADVANCE OF TRACKS WITHOUT SIGNALS OR GATES.
OR
8 FEET IN ADVANCE OF GATES.
OR
8 FEET IN ADVANCE OF SIGNALS WITHOUT GATES.

A PORTION OF THE "RXR" PAVEMENT MARKING SHOULD BE DIRECTLY OPPOSITE THE ADVANCE RAILROAD WARNING SIGN (W10-1).




GENERAL NOTES

- WHERE CENTER LINES OR EDGE LINES DO NOT EXIST, "RXR" SYMBOL MARKINGS SHALL EXTEND 6 INCHES FROM THE EDGE OF PAVEMENT TO 8 INCHES FROM THE CENTER LINE OF THE ROADWAY OR THE MARKING SHALL BE POSITIONED TO ACCOMMODATE FUTURE PLACEMENT OF EDGE LINE AND CENTER LINE PAVEMENT MARKINGS.
- ON MULTILANE ROADS, THE TRANSVERSE BANDS SHALL EXTEND ACROSS ALL APPROACH LANES AND INDIVIDUAL "RXR" SYMBOLS SHALL BE USED IN EACH APPROACH LANE. THE 24 INCH TRANSVERSE BANDS ARE NOT CONSIDERED A PART OF THE "RXR" SYMBOL PAY ITEM.
- ALL TRANSVERSE BANDS AND STOP BARS SHALL BE POSITIONED PERPENDICULAR TO THE CENTERLINE OF THE ROADWAY.
- FOR ROADWAYS LESS THAN 16 FEET IN WIDTH, THE "RXR" SYMBOL SHALL BE CENTERED ACROSS THE ENTIRE ROADWAY.
- REFER TO SIGNING PLANS OR STD. DWG. 1205.06-SHEET 3 FOR "D" ADVANCE WARNING SIGN PLACEMENT DISTANCE.
- REFER TO "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" OR SIGNING PLANS FOR ADDITIONAL WARNING SIGNS.


LEGEND

- ➔ DIRECTION OF TRAFFIC FLOW
- ⊗ PAVEMENT MARKING SYMBOLS
- ||||| RAILROAD TRACKS




d:\idq\12051102.dgn May 25, 1999 13:36:41


RAILROAD 40 TO 75 FT. FROM INTERSECTION




3-LANE SECTION
CENTER TURN-LANE DISCONTINUED ACROSS TRACKS




RAILROAD 40 TO 75 FT. FROM INTERSECTION




3-LANE SECTION
CENTER TURN-LANE CONTINUED ACROSS TRACKS




3-LANE, 2-WAY SECTION
(NO CENTER TURN-LANE)




5-LANE SECTION
CENTER TURN-LANE DISCONTINUED ACROSS TRACKS



5-LANE SECTION
CENTER TURN-LANE CONTINUED ACROSS TRACKS



TURN LANES AT RAILROAD CROSSING




GENERAL NOTES


- MARKERS ARE GENERALLY NOT REQUIRED ALONG EDGE LINES, EXCEPT IF DESIGNATED IN THE PLANS, OR DIRECTED BY THE ENGINEER. WHEN THEY ARE REQUIRED, THEY SHALL BE SPACED ON 20 FT. CENTERS, AND OFFSET 2 INCHES FROM THE EDGE LINE ON THE TRAFFIC SIDE.
- CRYSTAL/RED MARKERS SHOULD BE PLACED AT INTERSECTIONS AND INTERCHANGES WHERE WRONG-WAY MOVEMENTS ARE POSSIBLE. THE RED SIDE OF THE MARKER SHALL BE POSITIONED TO FACE "WRONG-WAY" TRAFFIC. WHEN USED, CRYSTAL/RED MARKERS SHOULD BE PLACED ALONG THE ENTIRE LENGTH OF THE PROJECT.
- PAVEMENT MARKER SPACING ALONG THRU LANES SHOULD BE REDUCED AS SHOWN ON THE SPACING CHART WHERE EXCESSIVE AMBIENT LIGHT FROM HIGHWAY ILLUMINATION SYSTEMS, OR OTHER FIXED SOURCES COULD REDUCE THEIR EFFECTIVENESS (0.8 FT.-CANDLES OR GREATER ON ANY 1000 FT. SECTION OF ROADWAY).
- PAVEMENT MARKERS SHOULD NOT BE PLACED CLOSER THAN 2 INCHES TO A PAVEMENT CONSTRUCTION JOINT (AS FEASIBLE), EXCEPT WHEN PLACED BETWEEN DOUBLE YELLOW CENTER LINES, AND ALONG YELLOW SKIP LINES ON TWO-LANE, TWO-WAY ROADWAYS WHERE PASSING IS ALLOWED IN BOTH DIRECTIONS.
- PAVEMENT MARKERS SHALL NOT BE PLACED DIRECTLY ON PAVEMENT MARKING LINES.
- PAVEMENT MARKERS USED IN CONJUNCTION WITH DOUBLE YELLOW CENTER LINES SHALL BE PLACED MID-WAY BETWEEN THE LINES, PROVIDED WITH A GAP BETWEEN THE LINES AND THE MARKER TO REDUCE OVERSPRAYING THE MARKER DURING REPAINTING OPERATIONS.
- MARKERS ARE NOT REQUIRED ALONG MINI-SKIP LINES IN TAPERS.

PAVEMENT MARKER SPACING CHART			
TYPE OF PAVEMENT MARKING	TYPICAL SPACING (FT)		SPEED LIMIT ≤ 45 M.P.H. OR AMBIENT LIGHT
	> 45 M.P.H.	80 40	
SKIP LINES AND CENTER LINES ALONG THRU LANES			
ALONG TANGENT SECTIONS AND HORIZONTAL CURVES LESS THAN 6°			40
HORIZONTAL CURVES > 6°			40
TURN-LANES - SKIP LINES SOLID LINES CENTER LINES			40 20 40
MINI-SKIP LINES AT LANE DROP APPROACHES			30
TWO-WAY RAMP CENTER LINES			40
GORE LINES			20
PAINTED ISLANDS - WHITE YELLOW			20 40
RAISED MEDIAN ISLANDS			40
WRONG WAY RAMP ARROW			5
TAPERS			40
NARROW BRIDGES - EDGE LINE CENTER LINE			20 40
ONE LANE BRIDGES- EDGE LINE			20
WORK ZONE APPLICATIONS			
2-LANE, 2-WAY BYPASS DIVERSIONS	20 FT. FOR CENTER LINE		
ALL OTHER DIVERSIONS	1/2 NORMAL SPACING		


PLACEMENT ALONG WHITE SKIP LINES




PLACEMENT ALONG WHITE / BLACK SKIP LINES




PLACEMENT ALONG WHITE
MINI-SKIP LINES




DETAIL OF PAVEMENT
MARKER PLACEMENT



PLACEMENT ALONG WHITE GORE LINES




PLACEMENT ALONG YELLOW CENTER LINES



LEGEND

- CRYSTAL / CRYSTAL PAVEMENT MARKER
OR
CRYSTAL / RED PAVEMENT MARKER
- YELLOW / YELLOW PAVEMENT MARKER
- DIRECTION OF TRAFFIC FLOW


AUXILIARY TURN LANES




LEGEND

- CRYSTAL/CRYSTAL PAVEMENT MARKER
OR
- CRYSTAL/RED PAVEMENT MARKER
- YELLOW/YELLOW PAVEMENT MARKER
- DIRECTION OF TRAFFIC FLOW

WHITE PAINTED ISLANDS




YELLOW PAINTED ISLANDS




TYPICAL PAVEMENT MARKER

TOP VIEW




LENS A	LENS B
YELLOW	YELLOW
CRYSTAL	RED
CRYSTAL	CRYSTAL

FRONT VIEW





SIDE VIEW





GENERAL NOTES

- THE AREA OF EACH REFLECTIVE LENS SHALL BE MINIMUM OF 2 SQUARE INCHES.
- FOR A COMPLETE LISTING OF PAVEMENT MARKERS AND ADHESIVES ACCEPTABLE FOR USE IN THIS STATE, REFER TO THE NCDOT APPROVED PRODUCTS LISTING AVAILABLE THROUGH THE DESIGN SERVICES UNIT, RALEIGH, NC.



NOTES
WIRE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
FILTER FABRIC SHALL BE A MINIMUM OF 36" IN WIDTH AND SHALL BE FASTENED ADEQUATELY TO THE WIRE AS DIRECTED BY THE ENGINEER.
STEEL POST SHALL BE 5'-0" IN HEIGHT AND BE OF THE SELF-FASTENER ANGLE STEEL TYPE.
WOOD POST SHALL BE 6'-0" IN HEIGHT AND 3" IN DIAMETER.





■ MATERIAL 2 IS OF A HIGHER QUALITY THAN MATERIAL 1.

PAVEMENT	COMBINATION OF SUBBASE, BASE AND SURFACE CONSTRUCTED ON SUBGRADE
SURFACE COURSE	A HOT MIXED BITUMINOUS CONCRETE DESIGNED AS A STRUCTURAL MEMBER WITH WEATHER AND ABRASION RESISTING PROPERTIES. MAY CONSIST OF WEARING AND INTERMEDIATE COURSES.
PRIME COAT	APPLICATION OF A LOW VISCOSITY LIQUID BITUMEN TO THE SURFACE OF THE BASE COURSE. THE PRIME PENETRATES INTO THE BASE AND HELPS BIND IT TO THE OVERLYING BITUMINOUS COURSE.
SEAL COAT	A THIN BITUMINOUS SURFACE TREATMENT CONTAINING AGGREGATE USED TO WATERPROOF AND IMPROVE THE TEXTURE OF THE SURFACE COURSE.
COMPACTED SUBGRADE	UPPER PART OF THE SUBGRADE WHICH IS COMPACTED TO A DENSITY GREATER THAN THE SOIL BELOW.
TACK COAT	A LIGHT APPLICATION OF LIQUID OR EMULSIFIED BITUMEN ON AN EXISTING PAVED SURFACE TO PROVIDE A BOND WITH THE SUPER-IMPOSED BITUMINOUS COURSE.
SUBGRADE	NATURAL IN-PLACE SOIL OR FILL MATERIAL.

REFERENCE: NAVY DM 21.3; ARMY TM 5-825-2; AIR FORCE AFM 88-6,
CHAPTER 2, FLEXIBLE PAVEMENT DESIGN FOR AIRFIELDS


TYPICAL FLEXIBLE PAVEMENT STRUCTURE
AND TERMINOLOGY

DATE
AUG 1978

42



NOT TO SCALE
Revised in accordance with amendment No. 0002




NOTE:

GRADE SHOULDER MATERIAL TO LEVEL OF MILLED ASPHALT SURFACE PRIOR TO APPLICATION OF ASPHALT OVERLAY.

OVERLAY X-SECTION (MILLED SURFACE & NO CURB)

NOT TO SCALE

Revised in accordance with amendment No. 0002





NOTE:

THICKNESS OF OVERLAY SPECIFIED BY
EXISTING FIELD CONDITIONS WILL BE
MEASURED AT THE Q OF THE ROADWAY.


OVERLAY OF ROADWAY (MILLED SECTION, CURB & NO GEOTEXTILE)

NOT TO SCALE


REPAIR OF POTHOLES



STEP 1: TRIM (VERTICAL SIDES) TO FIRM MATERIAL AND COMPACT



STEP 2: TACK COAT SIDES OF PATCH



STEP 3: PLACE HOT ASPHALT MIX IN LAYERS NOT TO EXCEED 3 IN; COMPACT AND LEVEL TO SPECIFIED GRADE AND DENSITY


REFERENCE: THE ASPHALT INSTITUTE MANUAL
SERIES MS-16 ASPHALT IN PAVEMENT
MAINTENANCE

REPAIR OF FLEXIBLE PAVEMENTS (POTHOLES)

DATE
JAN 1987

101181
2-1187

DEEP PATCH REPAIR




REMOVE SURFACE AND
BASE AS NECESSARY TO
FIRM MATERIAL AND COMPACT.

CUT STRAIGHT & VERTICAL
FACES (PAVEMENT SAW)

APPLY TACK COAT
VERTICAL FACES

HOT ASPHALT MIX PLACED
DIRECTLY ON SUBGRADE
NEEDS NO PRIME; PLACE
IN LAYERS NOT TO EXCEED 3 IN.



BACKFILL AND COMPACT
USING HOT ASPHALT MIX

VIBRATORY PLATE COM-
PACTOR (SM PATCHES)

ROLLER COMPACTOR
(LARGE PATCHES)


COMPACT TO SAME
GRADE AS SURROUNDING
PAVEMENT AND MEET
DENSITY REQUIREMENTS

REFERENCE: THE ASPHALT INSTITUTE MANUAL
SERIES MS-16 ASPHALT IN PAVEMENT
MAINTENANCE

REPAIR OF FLEXIBLE PAVEMENTS (DEEP PATCH)

DATE
JAN 1987

CRACK REPAIR




THE VARIABLE WIDTH AND AMOUNT OF SPALLING FOUND IN CRACKS
NECESSITATES DIFFERENT PROCEDURES FOR REPAIR


REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10,
REPAIR OF RIGID PAVEMENTS USING
EPOXY RESIN GROUTS, MORTARS AND
CONCRETE

REPAIR OF CONCRETE PAVEMENTS (CRACK)

DATE
JAN 1978




PAVEMENT THICKNESS LESS THAN 9 INCHES



NOTE: IF LANES GREATER THAN 20 FEET WIDE ARE USED, LONGITUDINAL CONTRACTION JOINTS MUST BE PLACED IN THE CENTER OF EACH LANE. TIE BARS WILL BE USED IN OUTSIDE LONGITUDINAL CONTRACTION JOINTS.

PAVEMENT THICKNESS 9 TO 12 INCHES



NOTE: IF PAVING LANES GREATER THAN 25 OR 20 FEET FOR AIR FORCE ARE USED, LONGITUDINAL CONTRACTION JOINTS MUST BE PLACED IN CENTER OF EACH LANE.


PAVEMENT THICKNESS GREATER THAN 12 INCHES

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

TYPICAL JOINTING - PLAIN CONCRETE PAVEMENT

DATE
AUG 1988

LONGITUDINAL




REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

CONTRACTION JOINT (LONGITUDINAL) FOR
PLAIN CONCRETE PAVEMENTS

DATE
AUG 1988

TRANSVERSE



Dⁿ DENOTES DOWEL DIAMETER

PAVEMENT THICKNESS IN.	MINIMUM DOWEL LENGTH IN.	MAXIMUM DOWEL SPACING IN.	DOWEL DIAMETER AND TYPE
<8	16	12	3/4-IN. BAR
8 TO 11.5	16	12	1-IN. BAR
12 TO 15.5	20	15	1-TO 1-1/4-IN. BAR, OR 1-IN. EXTRA-STRENGTH PIPE
16 TO 20.5	20	18	1-TO 1-1/2-IN. BAR, OR 1- TO 2-1/2-IN. EXTRA-STRENGTH PIPE
21 TO 25.5	24	18	2-INCH BAR, OR 2-INCH EXTRA STRENGTH PIPE
>26	30	18	3-INCH BAR, OR 3-INCH EXTRA STRENGTH PIPE


REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

EXPANSION JOINT (TRANSVERSE) FOR
PLAIN CONCRETE PAVEMENTS

DATE
AUG 1988

FIGURE
2-80

TRANSVERSE



D[■] DENOTES DOWEL DIAMETER

PAVEMENT THICKNESS, INCHES	SPACING, FEET
LESS THAN 9	12-1/2 TO 15
9 TO 12	15 TO 20
OVER 12 [■]	20 TO 25

[■] 20-FOOT MAXIMUM SPACING FOR AIR FORCE PAVEMENTS.


PAVEMENT THICKNESS IN.	MINIMUM DOWEL LENGTH IN.	MAXIMUM DOWEL SPACING IN.	DOWEL DIAMETER AND TYPE
<8	16	12	3/4-IN. BAR
8 TO 11.5	16	12	1-IN. BAR
12 TO 15.5	20	15	1-TO 1-1/4-IN. BAR, OR 1-IN. EXTRA-STRENGTH PIPE
16 TO 20.5	20	18	1-TO 1-1/2-IN. BAR, OR 1- TO 1-1/2-IN. EXTRA-STRENGTH PIPE
21 TO 25.5	24	18	2-INCH BAR, OR 2-INCH EXTRA STRENGTH PIPE
>26	30	18	3-INCH BAR, OR 3-INCH EXTRA STRENGTH PIPE

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

CONTRACTION JOINT (TRANSVERSE) FOR
PLAIN CONCRETE PAVEMENTS

DATE
AUG 1988

LONGITUDINAL OR TRANSVERSE




REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS


EXPANSION JOINT (LONGITUDINAL)
FOR PLAIN CONCRETE PAVEMENTS

DATE
AUG 1988

(A) DOWELED



(E) THICKENED EDGE *




* NOTE: THIS TYPE JOINT SHOULD BE USED ONLY WHEN EXISTING PAVEMENT IS TO BE REPLACED IN A SHORT PERIOD OF TIME, SINCE WITHOUT LOAD TRANSFER IT WILL DETERIORATE QUICKLY.

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

CONSTRUCTION JOINTS (DOWELED AND THICKENED EDGE)
BETWEEN NEW AND EXISTING FLAIN CONCRETE PAVEMENTS

DATE
AUG 1988

SEPARATING TAPE



V = WIDTH OF SEALANT RESERVOIR (SEE TABLE)

D = DEPTH OF SEALANT (LO TO $1.5 \times V$)

T = DEPTH OF INITIAL SAWCUT

a. 1/4 SLAB THICKNESS FOR PAVEMENTS LESS THAN 12 INCHES

b. 3 INCHES FOR PAVEMENTS 12-18 INCHES ■

c. 1/6 SLAB THICKNESS FOR PAVEMENTS MORE THAN 18 INCHES ■

■ DESIGNER MAY WANT TO CONSIDER REQUIRING 1/4 SLAB THICKNESS

TABLE

JOINT SPACING FT.	WIDTH IN.	
	MIN	MAX
< 25	1/2	5/8
25-50	3/4	7/8
> 50	1.0	1-1/8

NOTES : 1. SEPARATING TAPE OR NONABSORBENT TAPE REQUIRED TO PREVENT JOINT SEALANT FROM FLOWING INTO SAWCUT, TO SEPARATE NONCOMPATIBLE MATERIALS AND TO PREVENT JOINT SEALANTS FROM BONDING TO BOTTOM OF RESERVOIR.

2. TOP OF SEALANT WILL BE 1/8-IN. TO 1/4-IN. BELOW TOP OF PAVEMENT.


3. COMPRESSION SEAL MUST BE IN COMPRESSION AT ALL TIMES.

REFERENCE : TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

JOINT SEALANT DETAILS FOR AIRFIELD PAVEMENTS
(SEPARATING TAPE)

DATE
AUG 1988

DG 1110-3-204
 AFP 88-71
 30 April 1991



- W = WIDTH OF SEALANT RESERVOIR (SEE TABLE)
 D = DEPTH OF SEALANT (1.0 TO 1.5 X W)
 T = DEPTH OF INITIAL SAWCUT OR INSERT TYPE JOINT FORMER (CONTRACTION JOINT)
 a. 1/4 SLAB THICKNESS FOR PAVEMENTS LESS THAN 12 INCHES
 b. 3 INCHES FOR PAVEMENTS 12-18 INCHES*
 c. 1/6 SLAB THICKNESS FOR PAVEMENTS MORE THAN 18 INCHES*

TABLE


JOINT SPACING FT	WIDTH, IN.	
	MIN	MAX
< 25	1/2	5/8
25 - 50	3/4	7/8
> 50	1.0	1-1/8

NOTE. SOME SINGLE COMPONENT COLD APPLIED SEALANTS REQUIRE A SHAPE FACTOR (D/W) OF LESS THAN 1 TO PERFORM PROPERLY. IN THESE CASES, THE SHAPE FACTOR SHALL BE PER MANUFACTURER'S RECOMMENDATION.

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
 RIGID PAVEMENTS FOR AIRFIELDS

POURED JOINT SEALANT DETAILS (BACKER MATERIAL)
 (FOR RIGID PAVEMENT)

DATE
 AUG 1988



- V = WIDTH OF SEALANT RESERVOIR (SEE TABLE)
 D = DEPTH OF SEALANT (1.0 TO 1.5 x V)
 T = DEPTH OF INITIAL SAWCUT
 a. 1/4 SLAB THICKNESS FOR PAVEMENTS LESS THAN 12 INCHES
 b. 3 INCHES FOR PAVEMENTS 12-18 INCHES ■
 c. 1/6 SLAB THICKNESS FOR PAVEMENTS MORE THAN 18 INCHES ■
 ■ DESIGNER MAY WANT TO CONSIDER REQUIRING 1/4 SLAB THICKNESS

TABLE

JOINT SPACING FT	WIDTH IN	
	MIN	MAX
< 25	1/2	5/8
25-50	3/4	7/8
> 50	1.0	1-1/8


- NOTES : 1. SEPARATING TAPE OR NONABSORBENT TAPE REQUIRED TO PREVENT JOINT SEALANT FROM FLOWING INTO SAWCUT, TO SEPARATE NONCOMPATIBLE MATERIALS AND TO PREVENT JOINT SEALANTS FROM BONDING TO BOTTOM OF RESERVOIR.
 2. TOP OF SEALANT WILL BE 1/8-IN. TO 1/4-IN. BELOW TOP OF PAVEMENT.
 3. COMPRESSION SEAL MUST BE IN COMPRESSION AT ALL TIMES.

REFERENCE : TM 5-825-3/AFM 88-6, CHAPTER 3,
 RIGID PAVEMENTS FOR AIRFIELDS

JOINT SEALANT DETAILS (BACKER MATERIAL)
FOR AIRFIELD PAVEMENT

DATE
AUG 1988

FIGURE
2-13a



- W = WIDTH OF SEALANT RESERVOIR (SEE TABLE)
D = DEPTH OF SEALANT (1.0 TO 1.5 X W)
T = DEPTH OF INITIAL SAWCUT OR INSERT TYPE JOINT FORMER (CONTRACTION JOINT)
a. 1/4 SLAB THICKNESS FOR PAVEMENTS LESS THAN 12 INCHES
b. 3 INCHES FOR PAVEMENTS 12-18 INCHES
c. 1/6 SLAB THICKNESS FOR PAVEMENTS MORE THAN 18 INCHES

TABLE

JOINT SPACING FT	WIDTH, IN.	
	MIN	MAX
< 25	1/2	5/8
25 - 50	3/4	7/8
> 50	1.0	1-1/8

NOTE: SOME SINGLE COMPONENT COLD APPLIED SEALANTS REQUIRE A SHAPE FACTOR (D/W) OF LESS THAN 1 TO PERFORM PROPERLY. IN THESE CASES, THE SHAPE FACTOR SHALL BE PER MANUFACTURER'S RECOMMENDATION.


REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

POURED JOINT SEALANT DETAILS FOR RIGID PAVEMENTS
(SEPARATING TAPE)

DATE
AUG 1988

DG 1110-3-204
 AFP 88-71
 30 April 1991

PREFORMED COMPRESSION SEAL



DEPTH & WIDTH: AS RECOMMENDED BY MANUFACTURER
 PER TYPE OF SEAL BEING USED.
 (DEPTH NOT LESS THAN 1.5 INCHES)

TOP OF PREFORMED SEAL WILL BE 1/8 - 1/4 INCH BELOW
 PAVEMENT SURFACE

COMPRESSION SEAL MUST BE IN COMPRESSION AT ALL TIMES.


JOINT SPACING FT	WIDTH-IN.	
	MIN.	MAX.
< 25	1/2	5/8
25 - 50	3/4	7/8
> 50	1.0	1-1/8

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
 RIGID PAVEMENTS FOR AIRFIELDS

JOINT SEALANT DETAILS (PREFORMED COMPRESSION SEAL)
 FOR RIGID PAVEMENT

DATE
 JULY 1986

PREFORMED COMPRESSION SEAL



DEPTH & WIDTH : AS RECOMMENDED BY MANUFACTURER PER TYPE
OF SEAL BEING USED. (DEPTH NOT LESS THAN
1.5 INCHES)

TOP OF PREFORMED SEAL WILL BE 1/8 - 1/4 INCH BELOW PAVEMENT SURFACE


COMPRESSION SEAL MUST BE IN COMPRESSION AT ALL TIMES.

REFERENCE : TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS

JOINT SEALANT DETAILS (PREFORMED COMPRESSION SEAL)

DATE
JULY 1988

FULL DEPTH REPAIR




REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10, REPAIR OF RIGID PAVEMENTS USING EPOXY RESIN GROUTS, MORTARS AND CONCRETE

TM 5-822-9/AFM 88-6, CHAPTER 3, RIGID PAVEMENTS FOR AIRFIELDS DATED AUGUST 1988 FOR DOWEL AND TIE BAR SIZE AND SPACING




ACI 503R-80, "USE OF EPOXY COMPOUNDS WITH CONCRETE" FOR GUIDANCE ON BONDING UNHARDENED CONCRETE TO HARDENED CONCRETE.

REPAIR OF CONCRETE PAVEMENTS (FULL DEPTH)

DATE
JAN 1978



PARTIAL DEPTH REPAIR




MAKE VERTICAL SAWCUT 2" DEEP APPROX. 3" FROM DISTRESSED AREA
 REMOVE ALL CONCRETE AND LOOSE MATERIAL WITH IN SAWED AREA
 TO SOUND CONCRETE (3" MIN DEPTH)
 USE A SEPARATING MEDIUM TO MAINTAIN AND PROTECT JOINT
 USE A BONDING AGENT TO INSURE GOOD CONTACT
 BETWEEN EXISTING PAVEMENT AND PATCH.
 GROUT AND PATCH WITH 2" SLUMP CONCRETE.
 AFTER PATCH HAS CURED CLEAN JOINT AND APPLY JOINT SEALANT

REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10,
 REPAIR OF RIGID PAVEMENTS USING
 EPOXY RESIN GROUTS, MORTARS AND
 CONCRETE

REPAIR OF CONCRETE PAVEMENTS (PARTIAL DEPTH)

DATE
 JAN 1978

SPALL REPAIR



MAKE VERTICAL SAWCUT 2" DEEP APPROX. 3" FROM DISTRESSED AREA
 REMOVE ALL CONCRETE WITHIN SAWED AREA TO SOUND CONCRETE OR 3" MINIMUM
 DEPTH TO MAINTAIN AND PROTECT JOINT USE A SEPARATING MEDIUM.
 GROUT AND PATCH WITH EPOXY CONCRETE, AFTER CURING CLEAN JOINT AND
 APPLY JOINT SEALANT.


REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10,
 REPAIR OF RIGID PAVEMENTS USING
 EPOXY RESIN GROUTS, MORTARS AND
 CONCRETE

REPAIR OF CONCRETE PAVEMENTS (SPALL)


DATE
 JAN 1978

FULL DEPTH REPAIR

A.



B.



1 - 2

FORM AND PLACE CONCRETE IN ONE REPAIR SECTION AT A TIME

REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10,
REPAIR OF RIGID PAVEMENTS USING
EPOXY RESIN GROUTS, MORTARS AND
CONCRETE


TM 5-822-9/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS
DATED AUGUST 1988 FOR DOWEL
AND TIE BAR SIZE AND SPACING

ACI 503R-80, "USE OF EPOXY COMPOUNDS
WITH CONCRETE" FOR GUIDANCE ON
BONDING UNHARDENED CONCRETE TO
HARDENED CONCRETE

REPAIR OF CONCRETE PAVEMENTS (FULL DEPTH)

DATE
JAN 1978

FAILED KEY




REFERENCE: TM5-822-9/AFM 88-6, CHAPTER 10,
REPAIR OF RIGID PAVEMENTS USING
EPOXY RESIN GROUTS, MORTARS AND
CONCRETE

TM 5-822-9/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS
DATED AUGUST 1988 FOR DOWEL
AND TIE BAR SIZE AND SPACING

ACI 503R-80, "USE OF EPOXY COMPOUNDS
WITH CONCRETE" FOR GUIDANCE ON
BONDING UNHARDENED CONCRETE TO
HARDENED CONCRETE.

REPAIR OF CONCRETE PAVEMENTS (FAILED KEY)


DATE
JAN 1978



GROOVING DETAIL - PCC


NOTES: GROOVING SHOULD NOT BE ACCOMPLISHED: WITHIN 6 INCHES OF TRANSVERSE JOINTS OR TRANSVERSE WORKING CRACKS: THROUGH NEOPRENE COMPRESSION SEALS (FOR LONGITUDINAL JOINTS, THE TIP OF THE SEAL SHOULD BE $1/8$ " BELOW THE BOTTOM OF THE GROOVE); THE FIRST 1500 FEET FROM THE THRESHOLDS: THE FIRST 300 FEET EITHER SIDE OF AN ARREST BARRIER CABLE WHICH REQUIRES HOOK ENGAGEMENT FOR OPERATION: THROUGH IN-RUNNING LIGHTING FIXTURES OR SIMILAR ITEMS. GROOVES SHOULD TERMINATE 5' FROM PAVEMENT EDGE.

0 - $1 - 1/8 \pm 1/8$ - ARMY
1 - $1/2 \pm 1/8$ - AIR FORCE




GROOVING DETAIL - AC

REFERENCE: TM 5-824-1/AFM 88-6, CHAPTER 1,
GENERAL PROVISIONS FOR AIRFIELD
PAVEMENT DESIGN.
TM 5-825.2, FLEXIBLE PAVEMENT DESIGN



A. TRANSVERSE SECTION SHOWING REMOVAL



B. TRANSVERSE SECTION SHOWING CONSTRUCTION

REFERENCE: TM 5-825-3/AFM 88-6, CHAPTER 3,
RIGID PAVEMENTS FOR AIRFIELDS


TYPICAL CONCRETE PAVEMENT INLAY IN
EXISTING FLEXIBLE PAVEMENT

DATE
AUG 1988


CAR PARKING DIMENSIONS

WIDTH (FT)	RECOMMENDED RANGE OF CAR STALL WIDTH (SW)				
	8	9	10	11	12
SMALL CAR USE	■				
ALL DAY PARKER USE		■			
STANDARD CAR USE			■		
LUXURY AND ELDERLY USE			■		
SUPERMARKET AND CAMPER USE					
HANDICAPPED USE*					■

* MINIMUM REQUIREMENTS = 2 PER 100 STALLS AS SPECIFIED BY FEDERAL LAW;
PLACE CONVENIENT TO DESTINATION



DRIVEWAY WIDTHS					
SW	W	45°	60°	90°	VEHICLE TYPE
8'-0"	1	38'-9"	44'-2"	57'-2"	SMALL CARS
	2	36'-8"	42'-9"	57'-2"	
8'-6"	1	47'-8"	54'-0"	66'-0"	STANDARD CARS
	2	45'-2"	51'-8"	66'-0"	
9'-0"	1	46'-4"	53'-10"	66'-0"	STANDARD CARS
	2	44'-8"	51'-6"	66'-0"	
9'-0"	1	47'-9"	53'-8"	66'-0"	LARGE CARS
	2	45'-5"	51'-8"	66'-0"	
9'-6" & 10'-0"	1	47'-7"	52'-4"	66'-0"	LARGE CARS
	2	45'-3"	50'-8"	66'-0"	



HANDICAPPED PARKING
TYPICAL


REFERENCE: DOD 4270.1-M CONSTRUCTION CRITERIA; AIA STANDARDS.

TYPICAL HANDICAPPED CAR PARKING LAYOUT

DATE
DEC 1988

FIGURE 1


PRESENCE DETECTION CONFIGURATION DETAILS



NOTES

1. MAINTAIN 18" MIN. SPACING BETWEEN LEAD-IN CABLES IN PAVEMENT.
2. USE #4 METALLIC CONDUIT AT ALL PAVEMENT EDGES FOR LOOP WIRES LEAVING THE ROADWAY (REFER TO FIGURE 3 FOR SECTION DETAILS).
3. ALL LOOPS WIRED TO THE SAME DETECTOR UNIT SHALL BE WIRED IN SERIES.
4. ALTERNATE POLARITY OF ADJACENT LOOPS ATTACHED TO THE SAME DETECTOR UNIT SO THAT ELECTRICAL CURRENT FLOWS IN THE DIRECTION SHOWN ON LOOPS.
5. INSTALL CONDUIT BUSHINGS ON METALLIC CONDUITS.

PULSE DETECTION CONFIGURATION DETAILS



GENERAL NOTES

1. ALL DIMENSIONS ARE IN INCHES (IN) UNLESS OTHERWISE NOTED.
2. NUMBER OF TURNS OF WIRE IN EACH LOOP SHALL BE THE NUMBER INDICATED ON THE SIGNAL PLANS.
3. LOOP DIMENSIONS AND LOCATIONS SHALL BE AS SHOWN ON SIGNAL PLANS.
4. LOOPS SHALL BE LOCATED IN CENTER OF LANES UNLESS OTHERWISE SHOWN ON PLANS.


FIGURE 2

LOOP WINDING AND SAW CUT DETAILS

NOTES


1. OPTION 2 IS THE PREFERRED SAW CUT METHOD FOR POOR PAVEMENT. PAVEMENT CONDITION TO BE DETERMINED BY ENGINEER.
2. OVERLAP SAW CUTS AT CORNERS AND INTERSECTION POINTS TO ENSURE UNIFORM SAW SLOT DEPTH.
3. TAG AND LABEL LOOP WIRE LEADS TO FACILITATE THE SPLICING OF SERIES AND ALTERNATE POLARITY CONNECTIONS.
4. TWIST LOOP WIRE LEADS SYMMETRICALLY FROM THE PAVEMENT EDGE TO THE PULL BOX AT A RATE OF NOT LESS THAN 15 TWISTS PER FEET.

LOOP WIRE TWISTING METHOD




QUADRUPOLE LOOP

SAW CUT OPTIONS



LOOP WINDING METHOD




SAW SLOT DEPTH CHART

DEPTH (IN)	NO. OF WIRE LAYERS					
	2	3	4	5	6	
CONCRETE	2	2	2.8	2.8	3	
ASPHALT	2	2.8	3	3	3	


FIGURE 3

LOOP WIRE PAVEMENT EDGE DETAILS


LOOP WIRE AT 30.4 IN CURB & GUTTER SECTION



LOOP WIRE AT 18.0 IN CURB & GUTTER SECTION



LOOP WIRE AT PAVEMENT SECTION




NOTES

1. USE 1/2 IN. METALLIC CONDUIT AT ALL PAVEMENT EDGES FOR LOOP WIRES LEAVING THE ROADWAY.
2. EXCAVATION UNDER CURB AND GUTTER SECTIONS FOR CONDUIT INSTALLATION IS NOT ALLOWED.
3. FOR LOOP WIRE AT 30.4 IN CURB & GUTTER SECTION INSTALL 20 mm X 300 mm PVC SLEEVE AND BEGIN TWISTING LEADS AS SHOWN.
4. INSTALL TWISTED LEAD-INS THROUGH CONDUIT AS SHOWN.
5. AFTER LOOP WIRE IS PLACED INTO SAW SLOTS, AND PRIOR TO SEALING SAW SLOTS OR SPLICING LOOP WIRE LEAD-INS TO LEAD-IN HOMERUN CABLE, TEST LOOP WIRES IN ACCORDANCE WITH SECTION 17.8.2.13.
6. PRIOR TO SEALING LOOPS, PLUG CONDUIT TO PROVIDE A WATER PROOF BARRIER AND PREVENT LOOP SEALANT FROM ENTERING CONDUIT WHERE LOOP WIRE LEAVES PAVEMENT SURFACE.


FIGURE 4

LOOP WIRE SPLICE POINT DETAILS

LOOP WIRE AT PULL BOX



LOOP WIRE AT POLE




NOTES


1. ALL LOOP WIRES/HOMERUN CABLE SPLICES SHALL BE MADE IN PULL BOXES OR APPROVED CONDUITS.
2. PULL BOXES SHOULD BE LOCATED A MINIMUM OF 6 IN. BEHIND BACK OF CURB/FOR PAVEMENT SECTIONS, A MINIMUM OF 6 FT FROM THE PAVEMENT EDGE, OR WITHIN THE R/W.

FIGURE 6

SPLICING FOR LEAD-IN CABLE AND LOOP WIRE




STEP 1. STRIP LOOP WIRE AND LEAD-IN CABLE



TWIST BARE CONDUCTORS TOGETHER AND SOLDER WITH RESIN CORE SOLDER

OR



CRIMP BARE CONDUCTORS TOGETHER WITH AN UNINSULATED BUTT CONNECTOR AND SOLDER WITH RESIN CORE SOLDER

BOND SHIELD DRAIN WIRE AT SPLICE SECTIONS (DO NOT GROUND)

STEP 2. CONNECT AND SOLDER (REFER TO FIG. 5)

ELECTRICAL TAPE



SHRINK TUBE



WIRE CAP

(FOR USE ONLY WITH SPLICE KIT)

OR



STEP 3. INSULATE EACH SOLDER JOINT SEPARATELY




FIGURE 5

LOOP WIRE AND LEAD-IN CABLE CONNECTION DETAILS

SINGLE CONNECTION

SERIES CONNECTION

PARALLEL CONNECTION



MOISTURE PROOF SEALANT OR SILICONE IMPREGNATED SHRINK TUBE

OR



SMALL PAPER CLIP OR OTHER SUITABLE CONTAINER

TIE OR TAPE WIRES AND CABLES TOGETHER AND DRESS THE LEADS CLOSE TOGETHER


AND

TOTALLY ENCAPSULATE SPLICE IN FLEXIBLE EMBEDDED SEALANT TO FORM A WATER-TIGHT SPLICE. ALLOW SEALANT TO SET.






STEP 4. ENVIRONMENTALLY PROTECT TOTAL SPLICE WITH MOISTURE PROOF SEALANT SPLICE KIT, OR SILICONE IMPREGNATED SHRINK TUBE

Reference: NCDOT
Traffic Signal Specifications




CHAIN LINK FENCE FABRIC TYPE FE-6

NOT TO SCALE




POST HINGE

V-BOLT HINGE DETAILS
(FOR GATES LESS THAN 6'-0" HIGH)
NOT TO SCALE





DROP BAR ASSEMBLY




LATCH ASSEMBLY


SWING GATE DETAILS
NOT TO SCALE



TRUSS ROD AND BAND DETAIL
NOT TO SCALE




C-SECTION LINE POST
BRACE RAIL AND CLAMP DETAILS
NOT TO SCALE




NOTE:
GROUND ROD TO BE INSTALLED AT SPECIFIED INTERVALS, AS PER SPECIFICATIONS.

FENCE GROUNDING DETAIL

NOT TO SCALE




END OR GATE POST



STRETCHING DETAILS

NOT TO SCALE




TOP RAIL BARBED WIRE SUPPORT ARM

NOT TO SCALE

GENERAL NOTES:

1. THIS STANDARD DRAWING CORRESPONDS TO THE REQUIREMENTS OF SAVANNAH DISTRICT GUIDE SPECIFICATIONS SECTION 02831.
2. DETAILS ARE TO CLARIFY REQUIREMENTS BUT ARE NOT INTENDED TO LIMIT OTHER FENCE SECTIONS AND METHODS OF INSTALLATIONS SPECIFIED.
3. BARBED WIRE SUPPORTING ARMS ARE TO POINT OUTWARD, UNLESS OTHERWISE NOTED.
4. GATES SHALL BE HINGED TO FREELY SWING 180° WITH A MAXIMUM CLEARANCE OF 2' WHEN CLOSED.




NOTES:

1. METAL POST TO BE GALVANIZED. ALL BOLTS, NUTS, WASHERS, AND SCREWS MUST BE RUSTPROOF.
2. CONCRETE FOR FOOTING SHALL BE OF PORTLAND CEMENT AND HAVE A MIN. COMPRESSIVE STRENGTH OF 3000 P.S.I.
3. SIGNS WILL BE FABRICATED BY USING A REFLECTING COATING IN THE SYMBOL, MESSAGE AND BORDERS APPLIED TO A SHEET ALUMIN. BACKING (.080") IN THICKNESS
4. MESSAGE LETTERING SHALL BE UPPER CASE (WHITE SERIES B) 2" HIGH IN ACCORDANCE WITH MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
5. THE SYMBOL IS COMPOSED OF TWO ELEMENTS, A WHITE WHEELCHAIR FIGURE (WHICH SHOULD ALWAYS FACE RIGHT) ON A SQUARE BACKGROUND, INTERNATIONAL BLUE IN COLOR (FED. STD. 595A, COLOR #15180).
6. SIGN POST SHALL HAVE MIN. 2.0' CLEARANCE FROM BACK OF CURB.

SIGN FOR THE PHYSICALLY HANDICAPPED

NOT TO SCALE


SHEET 1 OF 1



BOLLARD DETAIL


NOT TO SCALE

SHEET 1 OF 1




NOTES:


CONCRETE WHEEL STOP DETAIL



IN CHANNELS ROLL OUT STRIPS OF NETTING
PARALLEL TO THE DIRECTION OF FLOW AND
OVER THE PROTECTIVE MULCH.*



ANCHOR NETTING
IN A 6" TRENCH.



JOIN STRIPS BY ANCHORING
AND OVERLAPPING.


* OMIT MULCH FOR JUTE MATTING.

INSTALLATION OF NETTING AND MATTING

NOT TO SCALE

INSTALLATION OF NETTING AND MATTING


NOT TO SCALE



TYPE B1 POLE AND BASE DETAIL

THE POLE SHALL BE CONSTRUCTED OF SEAMLESS SQUARE EXTRUDED ALUMINUM TUBE WELDED TO A CAST ALUMINUM BASE. A FLUSH CAST ALUMINUM POLE CAP SHALL BE PROVIDED. THE BASE SHALL HAVE A CAST ALUMINUM ANCHOR BOLT COVER SECURED TO THE BASE BY STAINLESS STEEL SCREWS THAT HAVE TO BE DRILLED TO BE REMOVED. THE HANDHOLE SHALL BE APPROXIMATELY 450mm ABOVE THE BASE AND SHALL INCLUDE A GASKETED COVER AND GROUND LUG. POLES AND FOUNDATIONS SHALL WITHSTAND STEADY WINDS OF 54 METERS PER SECOND (120 MILES PER HOUR) WHEN FIXTURES ARE MOUNTED TO POLE. PROVIDE A DRAINAGE CHANNEL THROUGH GROUT AT POLE BASE. ANCHOR BOLTS SHALL BE PRE-FABRICATED AND FURNISHED BY THE POLE MANUFACTURER. THE BASE SHALL BE REINFORCED WITH 4*8 VERTICAL REBAR AND WITH #3 HORIZONTAL REBAR 300mm ON CENTERS, 375mm LAP. ANCHOR BOLTS SHALL BE COORDINATED WITH AND TIED TO THE REINFORCING STEEL STRUCTURE OF THE BASE.


TYPE B1 POLE AND BASE DETAIL



TYPE B2 POLE AND BASE DETAIL

THE POLE SHALL BE CONSTRUCTED OF SEAMLESS SQUARE EXTRUDED ALUMINUM TUBE WELDED TO A CAST ALUMINUM BASE. A FLUSH CAST ALUMINUM POLE CAP SHALL BE PROVIDED. THE BASE SHALL HAVE A CAST ALUMINUM ANCHOR BOLT COVER SECURED TO THE BASE BY STAINLESS STEEL SCREWS THAT HAVE TO BE DRILLED TO BE REMOVED. THE HANDHOLE SHALL BE APPROXIMATELY 450mm ABOVE THE BASE AND SHALL INCLUDE A GASKETED COVER AND GROUND LUG. POLES AND FOUNDATIONS SHALL WITHSTAND **STEADY** WINDS OF 54 METERS PER SECOND (120 MILES PER HOUR) WHEN FIXTURES ARE MOUNTED TO POLE. PROVIDE A DRAINAGE CHANNEL THROUGH GROUT AT POLE BASE. ANCHOR BOLTS SHALL BE PRE-FABRICATED AND FURNISHED BY THE POLE MANUFACTURER. THE BASE SHALL BE REINFORCED WITH 4*8 VERTICAL REBAR AND WITH *3 HORIZONTAL REBAR 300mm ON CENTERS, 375mm LAP. ANCHOR BOLTS SHALL BE COORDINATED WITH AND TIED TO THE REINFORCING STEEL STRUCTURE OF THE BASE.

TYPE B2 POLE AND BASE DETAIL



COBRAHEAD ROADWAY LIGHT

TYPE HIGH PRESSURE SODIUM
400 WATT

HOUSING: THE FIXTURE SHALL INCLUDE A PRECISION DIE-CAST ALUMINUM UPPER AND LOWER HOUSING AND SHALL HAVE AN ELECTROCOAT GRAY PAINT FINISH. THE LOWER HOUSING SHALL BE HINGED AND SEPARABLE AND SHALL HOLD THE REFRACTOR IN PLACE. A BOLT-ON SLIPFITTER SHALL SECURELY FASTEN THE FIXTURE TO A 30mm TO 50mm PIPE BRACKET AND SHALL ALLOW $\pm 5\%$ ADJUSTMENT FROM THE HORIZONTAL. THE FIXTURE SHALL INCLUDE A FACTORY INSTALLED POLYMER BIRD GUARD AND AN EXTERNAL QUICK RELEASE STAINLESS STEEL BAIL LATCH REQUIRING NO TOOLS AND OPERABLE WITH A LINEMAN'S GLOVES.

OPTICAL ASSEMBLY: THE OPTICAL ASSEMBLY SHALL CONTAIN AN ALUMINUM REFLECTOR AND A CHEMICALLY BONDED LIGHTWEIGHT NON-BREAKABLE GLASS FINISH ON BOTH THE INSIDE AND OUTSIDE SURFACES. ELASTOMER GASKETING SHALL BE PROVIDED BETWEEN THE REFLECTOR AND A HEAT AND IMPACT RESISTANT GLASS PRISMATIC REFRACTOR. CHARCOAL FILTERING SHALL ALSO BE PROVIDED.

ELECTRICAL: THE FIXTURE SHALL BE COMPLETELY PREWIRED AND SHALL INCLUDE A HIGH POWER FACTOR (0.90 MINIMUM) BALLAST WITH A PUBLISHED BALLAST FACTOR OF UNITY. FIXTURE SHALL INCLUDE A PREWIRED NO-TOOL PHOTOELECTRIC CONTROL RECEPTACLE WITH A FAIL-ON PHOTOELECTRIC CELL. THE FIXTURE SHALL BE UL LISTED FOR WET LOCATIONS.

TYPE EB
COBRAHEAD ROADWAY LIGHT